Sonny's
65MT-EDT
Exterior Detail Hybrid Tunnel System

Wash, Wax, Seal, Tire Shine & Dry

▶ *Up To* **75 Cars** *Per Hour!* ◀

Tunnel Equipment:	$176,320	**Support Equipment:**	$132,659

$308,979

INCLUDES

FUSION PROCESS™

☼ **10** High Performance **LED LIGHTS**

🔧 OPTIONAL Support Equipment

Vacuum Systems
Point of Sale
Pay Stations
Tunnel Controller
Water Management
Signage

Powder Coating Options

*Optional items shown may not be included in total price and do not include installation or powder coating. Site plans are FREE with any Complete Tunnel System purchase. Site-specific mechanical drawings are also furnished FREE after initial deposit and equipment package choices are finalized.

Over-Under Conveyor
- 65-foot Painted Front Wheel Pull
- Air Take-Up
- Hydraulic Drive
- SC78 Chain
- Direct-Connect Rollers
- 8ft x 25in Correlator
- Banana Peel Guide Rails
- Fiberglass Grating
- Kickoff Plate
- Tracking Bars

FUSION PROCESS™

65MT-EDT

Exterior Detail Hybrid Tunnel System

1 **Entrance Arch & Pre-Soak Applicators**

🔅 **2- LED Lights**

Mr. Foamer Fully Lit Pinnacle Arch. Dual CTA's. Dual Directional Bumper Applicator. Foaminator Maxx for Fusion Bath Application with LED Lights. Dual Directional Pre-Soak Arch.

2 **SFM901 Mitter Combo**

🔅 **1 - LED Light**

SFM901 Mitter with MicroClean. Hydraulic Entrance Straight Arm Wraps with Neoglide Hush. Attached Hydraulic Poodle Plus Tire Brush with 21" Neoglide Hush Rockers. Undercarriage Wash Manifold. Banana Hybrid Kit for Tri-Foam. Banana Foamer Set with LED Light for Fusion Prime Application.

3 **Omni 352 High-Pressure Wash**

🔅 **1 - LED Light**

Hydraulic Omni 352 Arch with Attached Octopus Mirror Blaster and Rinse Stream Maxx with LED Light for Fusion Rinse Application.

4 **SFM807 Side to Side Mitter**

🔅 **2 - LED Lights**

SFM807 Mitter with MicroClean. Attached 28" Hydraulic Neoglide Hush Rockers. Double-Drip Applicator with LED Light for Fusion Seal Application. Foaminator Maxx Stream with LED Light for Fusion Wax Application. Banana V-Jets for Fusion Rain Repel Application.

5 **RainMA Arch**

10' Rain Multi Arch with 3 Manifolds – Rinse, Drying Agent, Spot-Free Rinse with Wings and Attached Rain-Bar Mirror Rinse.

6 **90 HP Drying System**

🔅 **4 - LED Lights**

(3) Arches with (6) 15HP Producers with (1) Set of Pivoting Mammoths. All Blowers Have Gator Gates for Instant Air Control. Free-Standing Hydraulic Tire Seal. (4) LED Lights for Toaster Effect.

Free Vacuum Stations

65MT-EDT Required Support Equipment

▶ **Required Chemical Stations**
3-Panel Chemical Concierge Dispensing System with VFD Booster Pump.

▶ **Required Pump Stations**
(2) Single H25 High-Pressure Pumping Station. Waterfall Pump Station.

▶ **Required Hydraulic Power Packs**
(1) Twin 7.5HP, (2) 7.5HP, (2) 5HP, and (1) 3HP Hydraulic Power Packs.

▶ **Required Air Compressors**
(2) 7.5HP Vertical 80 Gallon Ingersoll Rand Compressor, and (1) Ingersoll Rand 32 CFM Air Dryer.

▶ **Required Control Systems**
(1) Motor Control Center, (1) Photo Eye Entrance System, (2) Entrance Tape Switches, (1) Conveyor Pulse Kit.

---

www.**SonnysDirect**.com | 1-800-327-8723

The Tunnel Experts™