Sonny's
160-EDT
Exterior Detail Hybrid Tunnel System

Wash, Wax, Seal, Tire Shine & Dry

Up To **180 Cars** *Per Hour!*

Tunnel Equipment: $410,214   **Support Equipment:** $205,347

$615,561

INCLUDES

FUSION PROCESS™

16 High Performance LED LIGHTS

OPTIONAL Support Equipment

Vacuum Systems
Point of Sale
Pay Stations
Tunnel Controller
Water Management
Signage

Powder Coating Options

*Optional items shown may not be included in total price and do not include installation or powder coating. Site plans are FREE with any Complete Tunnel System purchase. Site-specific mechanical drawings are also furnished FREE after initial deposit and equipment package choices are finalized.

FUSION PROCESS™

Over-Under Conveyor
- 160-foot Painted Rear Wheel Push
- Air Take-Up
- Hydraulic Drive
- Log Chain
- Direct-Connect Rollers
- 8ft x 25in Correlator
- Banana Peel Guide Rails
- Fiberglass Grating

SONNY'S®
The CarWash Factory

WASH MORE CARS

1 **Entrance Arch & Pre-Soak Applicators**

☼ **2 - LED Lights**

Mr. Foamer Fully Lit Pinnacle Arch. Dual CTA's. Dual Directional Bumper Applicator. Foaminator Maxx for Fusion Bath Application with LED Lights. Dual Directional Pre-Soak Arch.

2 **SFM901 Double Jog Spyder Wrap Combo**

☼ **1 - LED Light**

SFM901 Spyder with MicroClean Mitter. Hydraulic Entrance & Exit Double Jog Wraps with Neoglide Hush. Attached Hydraulic Poodle Plus Tire Brush with 21" Neoglide Hush Rockers. Undercarriage Wash Manifold. Banana Hybrid Kit for Tri-Foam. Banana Foamer Set with LED Light for Fusion Prime Application.

3 **Dual Action Grill Brush**

Hydraulic Dual Action Grill Brush with Neoglide Hush.

4 **Omni 352 & Pendulum High-Pressure Wash**

☼ **1 - LED Light**

Hydraulic Omni 352 Arch with Attached Octopus Mirror Blaster. Pendulum Wheel Washer with Spinner. Rinse Stream Maxx with LED Light for Fusion Rinse Application.

5 **DCW Top Brush Combo**

☼ **2 - LED Lights**

Electric Dual CounterWeight Top Brush with Neoglide Hush with LED Light. Attached Hydraulic Ninja Brush with 18" Hydraulic Neoglide Hush Rockers. Double-Drip Applicator with LED Lights for Fusion Seal Application.

6 **SFM807 Mitter Combo**

☼ **2 - LED Lights**

SFM807 Mitter with MicroClean. Attached 28" Hydraulic Neoglide Hush Rockers. Foaminator Maxx Stream with LED Light for Fusion Wax Application. Banana V-Jets for Fusion Rain Repel Application with LED Light.

7 **RainMA Arch**

10' Rain Multi Arch with 4 Manifolds – Rinse, Clear-Coat, Drying Agent, Spot-Free Rinse with Wings and Attached Rain-Bar Mirror Rinse.

8 **195 HP Drying System**

☼ **8 - LED Lights**

(5) Arches with (13) 15HP Producers with (1) Duck Bill and (2) Sets of Pivoting Mammoths. All blowers have Gator Gates™ for instant air control. (8) LED Lights for Toaster Effect.

9 **Buff-N-Dry & Tire Seal Combo™**

Electric Buff-N-Dry with Entrance Wraps and Wick-A-Way Velcro Drying Material. Attached Hydraulic Tire Seal and Mammoth Dryers.

160-EDT Required Support Equipment

Required Chemical Stations
3-Panel Chemical Concierge Dispensing System with VFD Booster Pump.

Required Pump Stations
(2) H25 Dual High-Pressure Pumping Stations.

Required Hydraulic Power Packs
(1) Twin 10HP, (5) 7.5HP, and (1) 5HP and (1) 3HP Hydraulic Power Packs.

Required Air Compressors
(2) 10HP Vertical 120 Gallon Ingersoll Rand Compressors, and (1) Ingersoll Rand 64 CFM Air Dryer.

Required Control Systems
(1) Motor Control Center, (1) Photo Eye Entrance System, (2) Entrance Tape Switches, (1) Conveyor Pulse Kit.